DOCUMENT 00 73 00

SPECIAL CONDITIONS

List and describe any Contract Conditions not covered under Document 00 72 00 General Conditions that are unique to this specific project.

- 1. Notice to Proceed shall be issued no later than April 26th, 2022.
- 2. Construction activities shall be staged such that east-west and north-south pedestrian crossings with the intersection of Angus Avenue and Huntington Avenue are maintained at all times. Payment for staging construction activities to maintain pedestrian crossings will be included in the various bid items and no separate payment will be made. Failure to maintain pedestrian crossing shall result in liquidated damages in the amount of \$500 per Calendar Day.
- Temporary pedestrian facilities must comply with the Caltrans Temporary Pedestrian Facilities Handbook available at (http://www.dot.ca.gov/hq/construc/safety/Temporary_Pedestrian_Facilities_Ha ndbook.pdf), the California Manual on Uniform Traffic Control Devices (CA MUTCD) Part 6, Chapter 6D – Pedestrian and Worker Safety (available at http://www.dot.ca.gov/trafficops/camutcd/docs/2014r2/CAMUTCD2014-Chap6D.pdf), and the Caltrans Design Information Bulletin 82-06 – Pedestrian Accessibility Guidelines for Highway Projects, Section 4.3.2 and Section 4.6, which require that CA MUTCD Part 6, Chapter 6D, be followed when temporary routes are provided.
- 4. Construction equipment and materials may be stored within the public right-ofway but must be moved every five (5) days as construction progresses. Material storage at the construction site shall be limited to what is needed for five (5) days construction. No construction material shall be stored over the weekend unless approved by the City Engineer. Operating reflector barricades shall be required for all equipment and material left on the street overnight. At the end of each workday all loose material, parts and debris must be cleaned up and discarded and any stored materials shall be neatly stacked and organized. Failure to comply with these requirements shall result in liquidated damages in the amount of <u>\$250</u> per <u>Calendar Day</u>.

-END OF DOCUMENT-

Attachment 4 - Construction Staging Requirements

(THIS PAGE IS LEFT BLANK INTENTIONALLY.)

Attachment 4 - Construction Staging Requirements